

PANEL SPLICE ASSEMBLY - 1



MIN. 6" WIDE HIGH TEMP UNDERLAYMENT STRIP TO TIE INTO ROOF UNDERLAYMENT

EXPLODED VIEW

STARTER CLEAT SET IN BUTYL TAPE
3 CONTINUOUS BEADS OF 1/4" DIA. BEADS OF BUTYL SEALANT

1" MIN.

FIELD TRIM TOP OF SEAM TO ALLOW FOR NESTING

HIGH TEMP UNDERLAYMENT

APPROPRIATE FASTENER

6" MIN.

FINISHED VIEW

NOTE: FIRST PANEL CLIP TO LAND WITHIN 8" OF PANEL END

3 CONTINUOUS BEADS OF 1/4" DIA. BEADS OF BUTYL SEALANT

SHEATHING

NOTE: STAGGER ADJACENT END LAPS MINIMUM of 12"

SP-1

Temple Architectural Products
1111 Lowell St.
Elyria, Ohio 44035

(440) 323-9393
Estimates@templearchitecturalproducts.com
www.templearchitecturalproducts.com

- 1) Temple Architectural Products provides generic details for estimating purposes only and assumes no liability for the weather-tight integrity of these details if installed incorrectly.
- 2) Wood nailer or blocking must be installed to meet applicable building codes and/or support 200 LB load in any given direction per linear foot.